PARK ROAD DRAINAGE IMPROVEMENTS TOWN OF INNISFIL

PUBLIC INFORMATION CENTRE

JANUARY 22, 2020









WELCOME

THIS PUBLIC INFORMATION CENTRE WILL:

- identify the project purpose and objective
- detail the work area
- seek input & comments for consideration in final design
- establish channels of communication with public & stakeholders

PUBLIC & STAKEHOLDERS SHOULD:

- sign-in
- review presentation material
- direct questions to Town and/or Consultant
- submit comment sheet & indicate whether or not you want to be kept informed of the process





BACKGROUND

Park Road is a local road extending from 25th Side Road to Florence Road that is currently experiencing drainage issues:

- high Lake Simcoe water levels back water into the drainage ditches along Park Road
- culverts are damaged/buried and sediment build-up reduces capacity
- large external drainage area coming into Park Road



OBJECTIVE


Objectives of this project are to:

- improve drainage characteristics of existing ditches and culverts along Park Road
- reduce flows coming into Park Road









LEGEND

EXISTING CULVERTS

CULVERTS TO BE REPLACED

EXTERNAL DRAINAGE AREA (34 Ha)

PARK ROAD DITCHES

PARK ROAD DRAINAGE IMPROVEMENTS - EXISTING CONDITION





PARK ROAD DRAINAGE IMPROVEMENT OPTIONS

1. DO NOTHING

- Conditions exist as-is

2. UPGRADE DITCHES ALONG PARK ROAD ONLY

- Improved drainage characteristics, but flow from the external area will continue to flow through Park Road

3. DIVERSION & RAISING OF DITCH ALONG PARK ROAD

- Flows to Park Road will be significantly less
- Ditches can be shallower but will impact many driveways
- Cover over driveway culverts will be minimal

4. DIVERSION & MAINTAIN CURRENT DITCH DEPTH ALONG PARK ROAD

- Flows to Park Road will be significantly less
- Ditches/culverts will be graded/replaced as required
- Less driveways impacted and proper cover will be provided for culverts





DESCRIPTION OF PROPOSED WORKS

Part 1: New Diversion Open Channel and Existing Outfall Channel to Lake Simcoe

- Install and maintain temporary erosion and sediment controls
- Construct diversion open channel through Innisfil Beach Park
- Re-grade outfall channel to Lake Simcoe
- Grading works to divert external drainage area into the new open channel
- Tree removals and protection as required throughout

Part 2 - Park Road Ditch and Culvert Works

- Install and maintain temporary erosion and sediment controls
- Ditch re-grading and culvert replacement on north and south side of Park Road
- Stabilization and restoration of work area on a weekly-basis until completion of works
- Town standards does not utilize culvert headwall. New culverts will utilize 3:1 slopes from edge of driveway.





POTENTIAL IMPACTS DURING CONSTRUCTION


- Work is planned during summer months
- Portions of Innisfil Beach Park will closed off for new open channel
- Access to Innisfil Beach Park through Alderslea will be limited
- One soccer field on the park will be closed
- Culvert replacement on Park Road and Alderslea Crescent may require traffic through Park Road to be re-routed. Road will be restored upon completion of crossing to minimize disruption
- All properties affected by culvert replacements will have their driveways re-instated on the same day to ensure no disruption to residents

Affected Innisfil Beach Park Area










PARK ROAD DRAINAGE IMPROVEMENTS - KEY PLAN







PARK ROAD DRAINAGE IMPROVEMENTS - IMPACTED AREAS





2194 MERRETT STREET



772 PARK ROAD







PARK ROAD DRAINAGE IMPROVEMENTS - IMPACTED DRIVEWAYS









708 PARK ROAD







PARK ROAD DRAINAGE IMPROVEMENTS - IMPACTED DRIVEWAYS





2194 ALDERSLEA CRES. & 708 PARK ROAD





767 PARK ROAD















753 PARK ROAD



















PARK ROAD DRAINAGE IMPROVEMENTS - IMPACTED DRIVEWAYS









2183 ALDERSLEA CRES. & 703 PARK ROAD



METRIC





PARK ROAD DRAINAGE IMPROVEMENTS - IMPACTED DRIVEWAYS/ROAD





PROJECT SCHEDULE

Estimated project schedule is as follows:

- March 2020: Arborist Report and Tree Removals
- April 2020: Finalize design, drawings and contract documents; obtain permits and approvals
- May 2020: Issue contract document for public tender
- June 2020: Review tender submissions and award contract to a General Contractor
- July 2020: Construction to begin
- October 2020: Construction complete





NEXT STEPS

- 1. Review and address comments received from public meeting
- 2. Complete project file report
- 3. Finalize design, drawings and contract documents
- 4. Obtain relevant permits and approvals
- 5. Construction planned for Summer of 2020

If you have more questions, please contact the Town or KSGS Engineering:

CONTACTS

Ms. Amber Leal, C.E.T

Capital Project Manager, Town of Innisfil 2101 Innisfil Beach Road. Innisfil, ON L9S 1A1

Phone: 705-436-3740 Ext. 3246

Email: aleal@innisfil.ca

Mr. Ken Chow, P. Eng

Project Manager, KSGS Engineering 470 Hensall Circle Mississauga, ON L5A 3V4

Phone: 416-818-6180

Email: ken.chow@ksgsengineering.com



